OFFICE OF THE PALACE ENGINEER, MYSORE.

Notification dated 7th June 1939.

The Palace House situated to the south west of SREE CHAMARAJESWARA TEMPLE AT CHAMARAJNAGAR will be sold by public auction on 16th July 1939 at the site at 10 A.M. by the Palace Engineer.

For conditions of sale, please apply to the undersigned.

N. NEELAKANTAPPA,
Palace Engineer.

SHIMOGA DIVISION.

Notification dated 5th June 1939.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Shimoga Division, up to 4 P.M. on Monday, 10th July 1939, for constructing Electrical Buildings at Sagar Town. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of December 1939.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Shimoga between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 1,000 in cash as earnest money, and be superscribed "Tender for constructing Electrical Buildings in Sagar Town" in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Superintending Engineer, Shimoga Circle, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender the successful competitor will be required to execute the usual contract bond, in default of which his tender will be considered cancelled and his earnest money will be forfeited.

A deduction of 5 per cent will be made in the work bills towards security deposit for the due fulfilment of the contract.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiry regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders the earnest money on rejected tenders will be returned.

9. Rates once tendered will not be enhanced on any account.

10. Rates for non tendered and non-estimated items shall be as per schedule rates of the Department or those fixed by the Executive Engineer after working out data with not more than 10 per cent for contractor's profit.

11. In all matters not specially provided for and in all matters of dispute about rates, quantities, measurement, quality of works, etc., and in all disputes of any kind, the decision of the Executive Engineer will be final and legally binding.

12. Quotations must be given in words, as well as in figures and they must be in specific term of unit shown against each item or work. Any quotation quoted at so much percentage less or more than the estimated rate will not be accepted.

13. Chamundy Brand cement should be used.

14. Teakwood should be purchased from Government Depots.

Constructing Station Building, Office and Stores (Drawing No. G. 399) at Sagar Town.

No.	Items of work	Unit	Rate	Quantity	Cost
			Rs. a. p.		
1	Earthwork excavation for foundations and removing the excavated earth to a distance of not exceeding 50 yards and filling in basement duly watering and tamping in layers of 6"	C.yd.	0 4 0	67	
2	Granite jelly concrete in Lime mortar (1 : 2) for foundation laid in layers of 6", well tamped including watering, etc.	C.ft.	0 4 6	605	
3	Laterite stone in clay for foundation and basement including bonds, etc., complete	C.ft.	0 4 6	1,262	
4	Laterite stone in lime mortar for superstructure ..	,,	0 6 6	2,350	
5	Cement concrete slab 6" thick plain for basement, and lintels over doors and windows, proportion (1 : 4 : 7) including, watering, curing, etc., complete	Sq.ft.	0 5 0	302	
6	Plastering with chunam mortar, two coats including rounding off corners for laterite stone wall and finishing smooth	Sqr.	4 8 0	43.16	

No.	Items of work	Unit	Rate	Quantity	Cost
			Rs. a. p.		
7	Pointing laterite stone masonry with cement mortar including racking out joints, etc., complete ..	Sqr.	5 0 0	2·50	
8	White and colour washing two coats	,,	0 5 0	45·66	
9	Cement concrete flooring with 1½″ cement concrete over a bed of 3″ lime concrete ½″ cement plastered on the top including cutting sqr. lines watering, etc., complete	,,	18 0 0	9·59	
10	Laterite stone in lime mortar pillars 1⅛′×1⅛′ with bond stones at intervals of 3′ to 4′ with base, capital, etc., complete including plastering and white washing two coats as shown in drawing complete	Each	20 0 0	6	
11	Reinforced cement concrete terrace for a pan not exceeding 10′ with necessary reinforcements including top and bottom plastering, white washing, etc., complete	Sqr.	85 0 0	5·83	
12	Parapet wall with laterite in lime mortar 9″ and 1½′ high with necessary pillasters with plastering and whitewashing, two coats complete ..	R.ft.	1 0 0	78	
13	Hoisting and providing rolled steel beams 6″×3″ including two coats of Lac Factory green paint, without boxing	Cwt.	15 0 0	13·5	
14	T. W. panelled door frames 4″×5″ section, shutters 1½″ thick including all fixtures, such as tower bolts, hinges, handles, etc., complete as per design approved	S.ft.	2 0 0	154	
15	T. W. windows with glazed shutters in four halves frames 4″×5″ outside battened shutters and inside glazed shutters with iron bars ⅝″ at 5″ c.to c. including all fixtures such as hinges, bolts, etc., complete as per approved design	S.ft.	2 12 0	123	
16	T. W. ventilators with glazed shutters with iron bars frames 3″×4″ including all fixtures, etc., complete.	S.ft.	1 8 0	68	
17	R. C. jally work in front as per design	,,	1 6 0	125	
18	Providing and fixing C. I. rain water down pipes 3″ diam., with 22 B. W. G.	R.ft.	0 10 0	60	
19	Providing and fixing 2″ G. I. pipe for flag staff ..	L. S.	..	..	
20	Boxing girders with cement concrete including plastering at sides, bottom complete, etc., in verandah ..	C.ft.	0 8 0	36	
21	Roofing with first class Mangalore tiles on T. W. reepers 2″×1″ including wood oiling to reepers, etc., complete	Sqr.	32 0 0	12·34	
22	T. W. wrought and put up including two coats of wood oiling	C.ft.	5 0 0	90·40	
23	T. W. partition with frames alround including doors and shutter arrangement with planks 1″ thick including all fixtures, etc., complete	S.ft.	1 4 0	225	
24	Painting with two coats of silicate paint to doors and windows and partitions, etc.	Sqr.	4 4 0	5·87	
25	Providing stone racks as per design	L. S.	..	..	
26	Providing and fixing slabs 4″ thick on 3″ lime concrete below rain water down pipes	S.ft.	0 8 0	40	
27	Providing opening with necessary lintels for incoming and outgoing lines	L. S.	..	..	
28	Teakwood finials ornamental	Each	4 8 0	2	
29	Teakwood pendents ornamental	,,	2 0 0	4	
30	Plain teak wood eave board 9″ including two coats of wood oiling 1″ thick	R.ft.	0 10 0	139	
31	Ridge tiles set in mortr and cement pointed (Mangalore pattern)	R.ft.	0 10 0	85	
32	Levelling ground	L. S.	..	..	
	Constructing a Senior Operator's Quarters at Sagar Town.				
1	Earthwork excavation for foundation and removing the excavated earth to a distance of not exceeding 50 yards and filling in basement duly watering and tamping in layers of 6″ thick	C.yd.	0 4 0	59	

No.	Items of work	Unit	Rate	Quantity	Cost
			Rs. a. p.		
2	Granite jelly concrete in lime mortar (1 : 2) for foundation laid in layers of 6″ well tamped including watering, etc., complete	C.ft.	0 4 6	442	
3	Laterite stone in clay for foundation and basement including bonds, etc., complete	C.ft.	0 4 6	1,379	
4	Laterite stone in clay for superstructure	,,	0 4 6	1,727	
5	Laterite stone in lime mortar for superstructure ..	,,	0 6 6	544	
6	Cement concrete slabs 6″ thick plain for basement and lintel over doors and windows proportion (1 : 4 : 7) including watering, curing, etc., complete	Sq.ft.	0 5 0	149	
7	Pointing laterite stone masonry with cement mortar including racking out joints, cutting lines, etc., complete	Sqr.	5 0 0	2·40	
8	Plastering with chunam mortar two coats including rounding off corners for laterite stone wall and finishing smooth, etc., complete	Sqr.	4 8 0	45·37	
9	White and colour washing two coats	,,	0 5 0	47·77	
10	Flooring with 1½″ cement concrete over a bed of 3″ lime concrete including plastering on the top ½″ thick cutting squares and watering, etc., complete.	,,	18 0 0	8·50	
11	Roofing with 1st class Mangalore tiles on T. W. reepers 2″×1″ including two coats of wood oiling.	,,	32 0 0	15·52	
12	Mangalore pattern ridge tiles set in mortar and cement pointed	R.ft.	0 10 0	73	
13	Teakwood wrought and put up including two coats of wood oiling	C.ft.	5 0 0	92·32	
14	Plain teak wood eaveboard 9″ with two coats of wood oiling 1″ thick	R.ft.	0 10 0	128	
15	T. W. doors with battened shutters frames 4″×5″ shutters 1½″ thick including all fixtures such as stoppers, bolts, tower bolts, handles, etc. complete as per design	S.fv.	1 12 0	163	
16	T. W. windows with battened shutters with iron bars ⅝″ diam. 5″ c. to c. including all fixtures such as handles, stoppers, bolts, etc., complete as per design	,,	2 0 0	110	
17	Mortar band 9″×9″ over tiled roof including plastering	R.ft.	0 6 0	26	
18	T. W. cupboards with battened shutters 1″ thick frames 3″×4″ including planks in the middle with all fixtures, etc., complete	S.ft.	1 8 0	48	
19	Teak wood screen with expanded metal with frame including door and shutter arrangements, etc., complete	,,	1 0 0	111	
20	Chocolate painting two coats to doors, windows, cupboards and screen	Sqr.	3 8 0	9·45	
21	Providing and fixing ventilating tiles	Each	2 8 0	6	
22	Constructing sinks in Bath	L. S.	..	..	
23	Constructing chimney	,,	..	..	
24	Providing and fixing mortar and pestle	Each	8 0 0	1	
25	Levelling ground	L. S.	..	..	
	Constructing a double block of Operator's Quarters at Sagar Town.				
1	Earthwork excavation for foundation and removing the excavated earth to a distance of not less than 50 yards and filling in basement duly watering and tamping in layers of 6″ thick	C.yd.	0 4 0	54	
2	Granite jelly concrete in lime mortar (1 : 2) for foundation laid in layers of 6″ well tamped including watering, etc., complete	C.ft.	0 4 6	602	
3	Laterite stone in clay for foundation and basement including bonds, etc., complete	,,	0 4 6	1,068	
4	Laterite stone in mud for superstructure ..	,,	0 4 6	1,981	
5	Laterite stone in lime mortar superstructure ..	,,	0 6 6	782	
6	Cement concrete slab plain 6″ thick for basement and lintel over doors and windows (1 : 4 : 7) ..	S.ft.	0 5 0	244	

No.	Items of work	Unit	Rate	Quantity	Cost
			Rs. a. p.		Rs.
7	Teakwood doors with battened shutters frames 4″×5″ shutters 1½″ thick including all fixtures such as stoppers, bolts, tower bolts, handles, etc., complete as per design	S.ft.	1 12 0	319	
8	Teakwood windows with battened shutters with iron bars ⅝″ diam. 5″ c. to c. including all fixtures such as stoppers, bolts, etc., as per design complete	,,	2 0 0	116	
9	Teakwood wall shelves with battened shutters frames 3″×4″ with planks in the middle including all fixtures such as hinges, bolts, stoppers, etc., complete	,,	1 8 0	96	
10	Teakwood wrought and put up including two coats of wood oiling	C.ft.	5 0 0	79·80	
11	Plain teak wood eaveboard 9″ including two coats of wood oiling and 1″ thick	R.ft.	0 9 0	152	
12	Roofing with 1st class Mangalore tiles on T. W. reepers 2″×1″ including two coats of wood oiling to reepers	Sqr.	32 0 0	18·40	
13	Mangalore pattern ridge tiles set in mortar and cement pointed	R.ft.	0 10 0	77	
14	Flooring with 1½″ cement concrete over a bed of 3″ to 4″ lime concrete and cement plastering ½″ including cutting squares rendering smooth, etc., complete	Sqr.	18 0 0	9·51	
15	Plastering with chunam mortar two coats including rounding off corners for laterite stone wall and finishing smooth, etc., complete	Sqr.	4 8 0	56·25	
16	Pointing laterite stone masonry (basement) with cement mortar including racking out joints, etc., complete	Sqr.	5 0 0	2·21	
17	White and colour washing two coats	,,	0 5 0	58·46	
18	Mortar band 9″×9″ including plastering whitewashing, finishing, etc., over Mangalore tile roofing complete	R.ft.	0 6 0	66	
19	Painting with chocolate paint two coats to doors, windows, wall shelves, etc., complete	Sqr.	3 8 0	14·13	
20	Teakwood screen with frames, etc., with expanded metal in the middle including door and shutter arrangements., etc., complete	S.ft.	1 0 0	123	
21	Constructing chimney	Each	10 0 0	2	
22	Constructing sinks in bath	,,	10 0 0	2	
23	Providing and fixing mortar and pestle	Set	8 0 0	2	
24	Levelling ground	..	..	..	

Constructing Accounts Clerks or lower subordinate quarters at Sagar Town.

1	Earthwork excavation for foundation and removing the excavated earth to a distance of not exceeding 50 yards and filling in basement duly watering and tamping in layers of 6″	C.yd.	0 4 0	37	
2	Granite jelly concrete in lime mortar (1 : 2) for foundation laid in layers of 6″ well tamped including watering, tamping, etc., complete	C.ft.	0 4 6	359	
3	Laterite stone in clay for foundation and basement including bond stones	,,	0 4 6	664	
4	Laterite stone in clay superstructure	,,	0 4 6	1,465	
5	Laterite stone in lime mortar superstructure	,,	0 6 6	375	
6	Cement concrete slab plain 6″ for basement and lintel over doors and windows (1 : 4 : 7)	S.ft.	0 5 0	119	
7	Plastering with chunam mortar two coats including rounding off corners and smothering it on laterite stone wall	Sqr.	4 8 0	35·98	
8	Pointing basement with cement mortar including racking out joints, etc., complete	Sqr.	5 0 0	1·14	
9	White and colour washing two coats	Sqr.	0 5 0	37·12	
10	Constructing sinks	Each	10 0 0	1	
11	Providing and fixing mortar and pestle	,,	8 0 0	1	

No.	Items of work	Unit	Rate	Quantity	Cost
			Rs. a. p.		Rs.
12	T. W. doors with battened shutters, frames 4″×5″ including all fixtures, such as bolts, stoppers, etc., complete as per design	S.ft.	1 12 0	137	
13	T. W. windows with battened shutters, frames 3″×4″ including iron bars $\frac{5}{8}$″ at 5″ c. to c. with all fixtures, such as bolts, hinges, stoppers, etc., complete as per design	,,	2 0 0	78	
14	T. W. cupboards with battened shutters including planks, hinges, bolts, etc., complete	,,	1 8 0	48	
15	Teakwood screen with frames and 1″ planks with door and shutter arrangement including all fittings, etc., as per design complete ..	,,	1 4 0	60	
16	T. W. wrought and put up including two coats of wood oiling	C.ft.	5 0 0	33·50	
17	Roofing with 1st class Mangalore tiles on T. W. reepers 2″×1″ including woodoiling	Sqr.	32 0 0	10·27	
18	Mangalore pattern ridge tiles set in mortar and cement pointed	R.ft.	0 10 0	26	
19	Mortar band 9″×9″ over tiled roof including plastering, etc., as per design complete	,,	0 6 0	64	
20	Providing and fixing ventilating tiles	Each	2 8 0	2	
21	Flooring with cement concrete 1½″ over a bed of 3″ to 4″ lime concrete and cement plastered over including cutting sq. tiles, etc., complete ..	Sqr.	18 0 0	4·95	
21*a*	T. W. or stone pillars with base and capital ..	Each	20 0 0	2	
22	Chocolate painting to doors and windows, two coats	Sqr.	3 8 0	6·00	
23	Levelling ground	L. S.	..	..	
24	Constructing drains, etc.	,,	..	..	

Constructing a block of four Line men's quarters at Sagar Town.

1	Earthwork excavation for foundation and removing the excavated earth to a distance of not exceeding 50 yards and filling in basement duly watering and tamping in 6″ layers	C.yd.	0 4 0	30	
2	Granite jelly concrete in lime mortar (1 : 2) for foundation laid in layers of 6″ well tamped including watering, etc., complete	C.ft.	0 4 6	329	
3	Laterite stone in clay for foundation and basement with bond stones	,,	0 4 6	740	
4	Laterite stone in mud superstructure	,,	0 4 6	1,347	
5	Laterite stone in lime mortar	,,	0 6 6	700	
6	Cement concrete slab 6″ plain including casting for basement and lintel (1 : 4 : 7)	S.ft.	0 5 0	150	
7	Plastering with chunam mortar two coats including rounding off corners, etc., and finishing smooth, etc., complete	Sqr.	4 8 0	43·06	
8	Pointing to basement with cement mortar including racking out joints, etc., complete	,,	5 0 0	1·50	
9	White and colour washing, two coats	,,	0 5 0	44·44	
10	Roofing with 1st class Mangalore tiles on T. W. reepers 2″×1″ including woodoiling	,,	32 0 0	15·00	
11	Mangalore pattern ridge tiles set in mortar and cement pointed	R.ft.	0 10 0	64·00	
12	Providing and fixing ventilating tiles	Each	2 8 0	16	
13	Teakwood wrought and put up including woodoiling	C.ft.	5 0 0	61·55	
14	T. W. battened doors as per specifications, frames 4″×5″, shutters 1¼″ thick including all fixtures, such as, stoppers, bolts, handles, etc., complete ..	S.ft.	1 12 0	234	
15	T. W. windows with battened shutters, frames 3″×4″ with iron bars $\frac{5}{8}$″ & 5″ c. to c. with all fixtures, etc., complete	,,	2 0 0	75	
16	Chocolate painting two coats to doors and windows	Sqr.	3 8 0	7·42	
17	T. W. wall shelf with frames and battened shutters with planks in the middle including all fixtures, etc., complete as per design	S.ft.	1 8 0	60	
18	Constructing sinks	Each	10 0 0	4	

No.	Items of work	Unit	Rate	Quantity	Cost
			Rs. a. p.		Rs.
19	Providing and fixing mortar and pestle	Set	8 0 0	4	
20	Flooring with 1½″ cement concrete over a bed of 4″ lime concrete cement plastered over and cutting sq. tiles, etc., complete	Sqr.	18 0 0	7·79	
21	Levelling ground	..	..	..	

D. A. HUKERI,
Executive Engineer.

CHITALDRUG DIVISION.

Abstract Notification dated 3rd June 1939.

The attention of the public is invited to the detailed notification calling for tenders for closing the breach of Mavinmadu tank, Hiriyur Taluk, published on pages 1102-1104, Part VI of the *Mysore Gazette*, dated 8th June 1939.

The last date for receiving tenders is 24th June 1939.

S. RAMASWAMY,
Executive Engineer.

MISCELLANEOUS DEPARTMENTS

OFFICE OF THE INSPECTOR-GENERAL OF POLICE IN MYSORE, BANGALORE.

Notice No. T. C. 295—37-38, *dated* 19*th November* 1937.

The public are hereby informed that an Avery's Weigh-bridge to weigh motor vehicles is erected in the Office of the Inspector-General of Police in Mysore, Cenotaph Road, Bangalore City, and that motor vehicles brought for weighment will be weighed on payment of a fee of Rs. 10 for each weighment. A certificate of weighment will invariably be issued with each weighment so made.

F. A. HAMILTON,
Inspector-General of Police.

OFFICE OF THE SUPERINTENDENT, GOVERNMENT GARDENS IN MYSORE, LAL-BAGH, BANGALORE.

Notification dated 3rd June 1939.

SUPPLY OF FRUIT AND OTHER PLANTS.

1. Sealed quotations are invited for the supply of the following fruit and other plants required for this Department for the period ending 30th June 1940.

2. The quotations should be addressed to the Superintendent, Government Gardens, Lal-Bagh, Bangalore, so as to reach him on or before 3 P.M., on 26th June 1939. Any quotation received after the above time and date will not be taken notice of.

3. Each quotation should be accompanied by an earnest money deposit of Rupees Fifty.

4. The successful contractor will be required to execute the contract bond on the usual Government Stamp paper within a week from the date of acceptance of contract, binding himself to the conditions for the due fulfilment of the contract, failing which his earnest money will be forfeited to Government and his contract rejected.

5. The deposit of the unsuccessful contractor will be refunded in due course and that of the successful contractor will be retained, till the end of his contract period.

6. The plants have to be supplied on indents, delivery being at the Lal-Bagh Nursery, Bangalore.

7. All plants supplied should be healthy and of good size and true to name.

8. The names of the varieties of different kinds of plants should be noted.

9. The rates should be quoted per single, dozen and hundred plants.

10. If any plants are found unsatisfactory for any reason, they should be replaced free of all charges.

11. The right of accepting or rejecting any quotation vests with the Superintendent, Government Gardens in Mysore, Bangalore, who is not bound to assign any reason for accepting or rejecting the lowest or any quotation.